INDEX

Section

General:
Certificate of ISO 9001: 2 Registration
Customer References
Partial Installation List

Pump Selection:
To Our Customers
Multi-Propeller Pump Performance Range

Engineering:
Sump Design guide

Factory Pump Test Facility Layout

Axial Flow Pumps:
Description Brochure
Axial Flow Pump Guide Specifications

Drawings:
Cross Sectional Line shaft Drawing
Pump Layout with R.A. Gear and Engine
Vertical Motor Driven Pump
Vertical Electric Belt/Sheave Drive
Vertical Pump with Right Angle Gear
Vertical Pump with V.H.S. Motor Drive
Vertical Pump with Sheave
Angle Pump with V.H.S. Motor Drive
Angle Pump with Belt/Sheave Drive
Angle Pump with R.A. Gear Drive
Angle Multi-Pump Layout Drawing

Axial Flow Performance Curves Section:

Mixed Flow Pumps:
Mixed Flow pump Guide Specifications

Mixed flow Performance Curves Section:

Submersible Electric Axial & Mixed Flow Pumps:
Description Brochure
S.E. Propeller Pump Guide Specifications
Cross sectional Drawing with Motor Coupled

Typical Discharge Tube Mounting Drawing
Pump Cross Section with Motor
Typical Horizontal/Angle Drawing
General Horizontal Pump Layout
S.E. Motor Brochures – Yeoman & Reliance
Auto Megger Testing Description

Portable Section:

Description Brochure
Hydraulic Pump Components & Cross Section Drawing
Portable Hydraulic Pump Guide Tech Specifications
Skid Mounted Drive Guide Tech Specifications

Mobile Pump Section:

Descriptive brochure
Mobile Pump Tech Guide Specifications
24" Hydraulic Mobile Drawing
General Mobile Drawing
Cross Sectional hydraulic Pump & Components

Trash Pump Section:

Portable Trash/Solids Brochure
Portable Guide Specifications

Associated Products:

Engine Selection Brochures
Right Angle Gear Brochures
Level Control Instrumentation
Check Valve Brochures
Air Release Valves
V.H.S. & V.S.S. Motor Brochures

Certificate of Registration

nqa global assurance

This is to certify that the Quality Management System of:

FPI Inc.
814 Hammondville Road
Pompano Beach, FL 33060

applicable to:

The design, manufacture, overhaul and repair of axial flow, mixed flow, centrifugal and mobile pumps

has been assessed and approved by
National Quality Assurance, U.S.A., against the provisions of:

ISO 9001:2008

For and on behalf
of NQA, USA, Acton, MA 01720

ANAB ACCREDITED

Certificate Number:	12543
EAC Code:	18
First Issued:	August 9, 2002
Valid Until:	September 26, 2011
Reissued:	September 30, 2009

This approval is subject to the company maintaining its system to the required standard, which will be monitored by NQA, USA, an accredited organization under the ANSI-ASQ National Accreditation Board.

Partial Installation List

FPI Inc.
814 Hammondville Road
Pompano Beach, FL 33060
(954) 946-3066 / (954) 946-3111 fax

Customer Name	Location	Units	Size	Year
Village of Wellington, FL	FL, USA	2	48"	2006
US Navy	WA, USA	4	24"	2006
US Army Corps-Jefferson Parish	LA, USA	3	60" Hyd	2006
US Army Corps-Jefferson Parish	LA, USA	1	36" Hyd	2006
US Army Corps-Jefferson Parish	LA, USA	5	24" Hyd	2006
US Army Corps-Jefferson Parish	LA, USA	6	20" Hyd	2006
Town of Ocean Ridge, FL	FL, USA	6	24" SE	2006
Town of Ocean Ridge, FL	FL, USA	4	16" SE	2006
US Fish and Wildlife	ID, USA	1	18" SE	2006
City of Indianapolis	IN, USA	6	42"	2006
Village of Wellington, FL	FL, USA	2	48"	2006
Wellton Mohawk Drainage Dist.	AZ, USA	2	42" Hyd.	2006
Florida Crystals	FL, USA	3	36"	2006
Florida Crystals	FL, USA	3	24"	2006
Florida Crystals	FL, USA	3	20"	2006
Republic of China	Taiwan	1	60"	2005
Village of Wellington, FL	FL, USA	1	36"	2005
Village of Wellington, FL	FL, USA	2	48"	2005
Slidell, LA	LA, USA	4	48"	2005
Department of Transportation	FL, USA	3	30"	2004
Terrebonne Parish, LA	LA, USA	1	48"	2004
US Bureau of Reclamation	TX, USA	6	42"	2004
US Bureau of Reclamation	TX, USA	2	30"	2004
Village of Wellington, FL	FL, USA	2	48"	2004
Village of Wellington, FL	FL, USA	1	36"	2004
SF Conservancy District, FL	FL, USA	1	42"	2004
City of Albany, GA	GA, USA	4	42"	2003
U.S. Army Corps of Engr., St. Paul	SD, USA	6	20"	2003
U.S. Army Corps of Engr., St. Paul	MN, USA	3	18"	2003
Palm Beach International Airport	FL, USA	8	42"	2003
Sunshine Water Control District	FL, USA	8	42"	2003
Barron Water Control	FL, USA	2	54"	2002
SF Water Management District	FL, USA	1	42" 2 stage	2002
Sugar Farms Coop (FL Crystals)	FL, USA	6	30"	2002
Hendry Hilliard Water Control	FL, USA	1	54"	2001
Northsprings Improvement Dist.	FL, USA	1	48"	2001

Village of Wellington, FL	FL, USA	1	**48"**	2001
IMC Agrico Inc.	FL, USA	2	**42" 2-stage**	2001
S. Broward Drainage Dist	FL, USA	3	**42"**	2001
Burt Washington Drainage Dist.	NE, USA	2	**42"**	2001
IMC Agrico Inc.	FL, USA	4	**42"**	2001
Acuicola San Esteban	Mexico	3	**36"**	2001
Coral Springs Imprvemnt Dist.	FL, USA	8	**54"**	2000
Brevard County, FL	FL, USA	1	**42" all SS**	2000
City of Weston, FL	FL, USA	2	**42"**	2000
Sugar Farms Coop (FL Crystals)	FL, USA	2	**36"**	2000
S. Broward Drainage Dist	FL, USA	3	**36"**	2000
S. Florida Water Mgt. Dist	FL, USA	2	**36"**	2000
Ishmael Construction	IL, USA	1	**36"**	2000
S. Broward Drainage Dist.	FL, USA	2	**30"**	2000
Barron Water Control	FL, USA	2	**48"**	1999
Aquacorporacion Inter.	Costa Rica	4	**42"**	1999
Gulf Coast Citrus Inc.	FL, USA	1	**36"**	1999
Sugar Farms Coop (FL Crystals)	FL, USA	8	**36"**	1999
A. Duda & Sons	FL, USA	1	**36"**	1999
Plattville Drainage Dist.	IA, USA	2	**36"**	1999
Boca West Masters Ass.	FL, USA	1	**36"**	1999
IMC Agrico Inc.	FL, USA	5	**42"**	1998
Barron Water Control	FL, USA	1	**54"**	1997
Barron Water Control	FL, USA	1	**48"**	1997
City of Hollywood, FL	FL, USA	2	**36"**	1997
Ideker Farms	MO, USA	1	**36"**	1997
Canadian Aquaculture Sys.	Canada	2	**36"**	1997
A. Duda & Sons	FL, USA	2	**36"**	1997
Deseret Ranch	FL, USA	9	**36"**	1997
U.S. Army Corps of Engr., Omaha	NE, USA	2	**48"**	1996
Acme Improvement District	FL, USA	4	**48"**	1996
U.S. Army Corps of Engr.	NE, USA	1	**48"**	1996
M&L Engine Co.	LA, USA	2	**48"**	1996
S. Broward Drainage Dist	FL, USA	8	**42"**	1996
Talisman Sugar	FL, USA	8	**42"**	1996
Sugar Farms Coop (FL Crystals)	FL, USA	9	**36"**	1996
ALICO Inc.	FL, USA	3	**36"**	1996
N. Palm Beach Improvement Dist.	FL, USA	2	**42" Hyd.**	1995
Loxahatchee Grove Water Cntrl.	FL, USA	1	**42"**	1995
Evans Properties	FL, USA	10	**30"- 42"**	1994
St. Charles Parish, LA	LA, USA	1	**36"**	1992
Barron Water Control	FL, USA	6	**54"**	1991

ALICO Inc.	FL, USA	6	**54"**	1990
Acme Improvement District	FL, USA	2	**54"**	1988
Deerfield Irrigation	FL, USA	3	**42"**	1988
Acme Improvement District	FL, USA	1	**54"**	1986
Fellsmere Farm	FL, USA	1	**42"**	1985
Boca West Masters Ass.	FL, USA	1	**42"**	1985
Fellsmere Farm	FL, USA	1	**36"**	1985
A. Duda & Sons	FL, USA	2	**54"**	1984
Sawgrass Players Club	FL, USA	3	**42"**	1983
W. Lauderdale Water Control	FL, USA	8	**36"**	1982
Fountain Bluff	IL, USA	2	**48" 2-stage**	1979
Hollywood Reclamation	FL, USA	2	**48"**	1979
Meekins Inc.	FL, USA	1	**42"**	1978
M.A. Kennedy	NY, USA	2	**54"**	1976
Hollywood Reclamation	FL, USA	2	**48"**	1976
Old Plantation Water Control	FL, USA	7	**48"**	1974
Hollywood Reclamation	FL, USA	2	**48"**	1973
Bonaventure	FL, USA	3	**42"**	1971
Weyerhauser Inc.	FL, USA	1	**48"**	1969
Lake Worth Drainage District	FL, USA	1	**48"**	1968
Talisman Sugar	FL, USA	4	**48"**	1967
Big B Ranch	FL, USA	8	**48"**	1967
Alapattah Properties	FL, USA	2	**42"**	1967



Partial Installation List

FPI Inc.
814 NW 3rd Street
Pompano Beach, FL 33060
(954) 946-3066 / (954) 946-3111 fax

Customer Name	Location	Units	Size	Year
Palm Beach Int. Airport	FL, USA	8	36"	2003
City of Georgetown, SC	SC, USA	1	30"	2002
Barron Water Control	FL, USA	2	54"	2002
Sunshine WCD	FL, USA	4	48"	2002
SFWMD	FL, USA	1	42" 2 stage	2002
GUYSUCO Ltd.	Guyana	1	30"	2002
Sugar Farms Coop (FL Crystals)	FL, USA	6	30"	2002
City of Hollwood, FL	FL, USA	2	24"	2002
Hendry Hilliard Water Control	FL, USA	1	54"	2001
Northsprings Improvement Dist.	FL, USA	1	48"	2001
Village of Wellington, FL	FL, USA	1	48"	2001
IMC Agrico Inc.	FL, USA	2	42" 2-stage	2001
S. Broward Drainage Dist	FL, USA	3	42"	2001
Burt Washington Drainage Dist.	NE, USA	2	42"	2001
IMC Agrico Inc.	FL, USA	4	42"	2001
Acuicola San Esteban	Mexico	3	36"	2001
City of Georgetown, SC	SC, USA	1	24"	2001
Coral Springs Imprvemnt Dist.	FL, USA	6	54"	2000
Brevard County, FL	FL, USA	1	42" all SS	2000
City of Weston, FL	FL, USA	2	42"	2000
Sugar Farms Coop (FL Crystals)	FL, USA	2	36"	2000
S. Broward Drainage Dist	FL, USA	3	36"	2000
S. Florida Water Mgt. Dist	FL, USA	2	36"	2000
Ishmael Construction	IL, USA	1	36"	2000
Plantation Acres Drainage Dist.	FL, USA	1	30"	2000
King Ranch	FL, USA	1	30"	2000
CR Pittman Inc.	LA, USA	2	30"	2000
Forrest Levee Drainage District	MO, USA	2	30"	2000
S. Broward Drainage Dist.	FL, USA	2	30"	2000
Barron Water Control	FL, USA	2	48"	1999
Aquacorporacion Inter.	Costa Rica	4	42"	1999
Gulf Coast Citrus Inc.	FL, USA	1	36"	1999
Sugar Farms Coop (FL Crystals)	FL, USA	8	36"	1999
A. Duda & Sons	FL, USA	1	36"	1999
Plattville Drainage Dist.	IA, USA	2	36"	1999
Boca West Masters Ass.	FL, USA	1	36"	1999

Deseret Ranch	FL, USA	1	30"	1999
S. Broward Drainage Dist	FL, USA	1	30"	1999
Industria Nacional	Dom. Rep.	1	24"	1999
IMC Agrico Inc.	FL, USA	5	42"	1998
Ishmael Construction	IL, USA	1	36"	1998
CFCO	IL, USA	1	30"	1998
H&H Sod Farm	FL, USA	1	24"	1998
City of Hollywood, FL	FL, USA	3	24"	1998
City of Lakeland, FL	FL, USA	1	24"	1998
CFCO	IL, USA	1	24"	1998
Bedner Growers Inc.	FL, USA	1	24"	1998
Barron Water Control	FL, USA	1	54"	1997
Barron Water Control	FL, USA	1	48"	1997
City of Hollywood, FL	FL, USA	2	36"	1997
Ideker Farms	MO, USA	1	36"	1997
Canadian Aquaculture Sys.	Canada	2	36"	1997
A. Duda & Sons	FL, USA	2	36"	1997
Deseret Ranch	FL, USA	9	36"	1997
Village of Bal Harbour, FL	FL, USA	2	30" all SS	1997
A. Duda & Sons	FL, USA	3	30"	1997
City of Tampa, FL	FL, USA	1	30"	1997
U.S. Army Corps of Engr.	NE, USA	2	48"	1996
Acme Improvement District	FL, USA	4	48"	1996
U.S. Army Corps of Engr.	NE, USA	1	48"	1996
M&L Engine Co.	LA, USA	2	48"	1996
S. Broward Drainage Dist	FL, USA	8	42"	1996
Talisman Sugar	FL, USA	8	42"	1996
Sugar Farms Coop (FL Crystals)	FL, USA	9	36"	1996
ALICO Inc.	FL, USA	3	36"	1996
Aqua Chame	Panama	10	30"	1996
Deseret Ranch	FL, USA	15	30"	1996
City of Jacksonville Beach, FL	FL, USA	2	24"	1996
Loxahatchee Grove Water Cntrl.	FL, USA	1	42"	1995
Boca West Masters Ass.	FL, USA	1	30"	1995
R&A Farms	FL, USA	6	30"	1995
Jensen of Jacksonville	FL, USA	4	24"	1995
Dade County, FL	FL, USA	1	24"	1995
Bombas Goulds de Ven.	Venezuela	3	36"	1994
Hendry Irrigation	FL, USA	1	36"	1994
Evans Properties	FL, USA	10	30"- 42"	1994
City of Parkland, FL	FL, USA	1	30"	1993
St. Charles Parish, LA	LA, USA	1	36"	1992

Town of Palm Beach, FL	FL, USA	1	**28"**	1992
St. John River Wtr Mgt	FL, USA	2	**24"**	1992
Barron Water Control	FL, USA	6	**54"**	1991
ALICO Inc.	FL, USA	6	**54"**	1990
City of Boca Raton, FL	FL, USA	1	**30"**	1990
City of Fort Lauderdale, FL	FL, USA	2	**30"**	1989
City of Boca Raton, FL	FL, USA	1	**30"**	1989
City of Fort Lauderdale, FL	FL, USA	1	**24"**	1989
Acme Improvement District	FL, USA	2	**54"**	1988
Deerfield Irrigation	FL, USA	3	**42"**	1988
Sunshine Drainage	FL, USA	1	**30"**	1988
Acme Improvement District	FL, USA	1	**54"**	1986
N. Palm Beach Wtr. Control	FL, USA	2	**42" Hyd.**	1985
Fellsmere Farm	FL, USA	1	**42"**	1985
Boca West Masters Ass.	FL, USA	1	**42"**	1985
Fellsmere Farm	FL, USA	1	**36"**	1985
A. Duda & Sons	FL, USA	2	**54"**	1984
Sawgrass Players Club	FL, USA	3	**42"**	1983
W. Lauderdale Water Control	FL, USA	8	**36"**	1982
Fountain Bluff	IL, USA	2	**48" 2-stage**	1979
Hollywood Reclamation	FL, USA	2	**48"**	1979
Meekins Inc.	FL, USA	1	**42"**	1978
M.A. Kennedy	NY, USA	2	**54"**	1976
Hollywood Reclamation	FL, USA	2	**48"**	1976
Old Plantation Water Control	FL, USA	7	**48"**	1974
Hollywood Reclamation	FL, USA	2	**48"**	1973
Bonaventure	FL, USA	3	**42"**	1971
Weyerhauser Inc.	FL, USA	1	**48"**	1969
Lake Worth Drainage District	FL, USA	1	**48"**	1968
Alapattah Properties	FL, USA	2	**42"**	1967
Talisman Sugar	FL, USA	4	**48"**	1967
Big B Ranch	FL, USA	8	**48"**	1967

Partial Installation List

FPI Inc.
FPI Pumps Inc
814 Hammondville Road
Pompano Beach, FL 33060
(954) 946-3066 / (954) 946-3111 fax

Customer Name	Location	Units	Size	Capacity	Year
GUYSUCO Ltd.	Guyana	1	30"	30,000 GPM	2002
Sugar Farms Coop (FL Crystals)	FL, USA	6	30"	18,000 GPM	2002
Sugar Farms Coop (FL Crystals)	FL, USA	1	24"	12,000 GPM	2002
City of Hollwood, FL	FL, USA	2	24"	12,000 GPM (w/cert. Fact. test)	2002
Cayman Turtle Farm	FL, USA	1	14" 3-stage All SS	5,000 GPM	2002
Terrebonne Parish, LA	LA, USA	2	12" Hyd	4,500 GPM	2002
Hendry Hilliard Water Control	FL, USA	1	54"	75,000 GPM (w/cert. Field test)	2001
Northsprings Improvement Dist.	FL, USA	1	48"	50,000 GPM (w/cert. Field test)	2001
Village of Wellington, FL	FL, USA	1	48"	50,000 GPM (w/cert. Field test)	2001
IMC Agrico Inc.	FL, USA	2	42" 2-stage	40,000 GPM	2001
S. Broward Drainage Dist	FL, USA	3	42"	45,000 GPM (w/cert. Fact. test)	2001
Burt Washington Drainage Dist.	NE, USA	2	42"	42,000 GPM	2001
IMC Agrico Inc.	FL, USA	4	42"	30,000 GPM	2001
Acuicola San Esteban	Mexico	3	36"	37,000 GPM	2001
City of Georgetown, SC	SC, USA	1	24"	15,000 GPM	2001
Ceatech Plantations	HI, USA	2	20"	10,000 GPM	2001
EPS Inc.	Puerto Rico	1	20"	10,000 GPM	2001
Evans Properties	FL, USA	2	20"	10,000 GPM	2001
IMC Agrico Inc.	FL, USA	2	18"	6,000 GPM	2001
Brevard County, FL	FL, USA	3	16" All SS	6,000 GPM	2001
Terrebonne Parish, LA	LA, USA	2	14" Hyd.	5,000 GPM	2001
Coral Springs Imprvemnt Dist.	FL, USA	6	54"	50,000 GPM (w/cert. Fact. test)	2000
Brevard County, FL	FL, USA	1	42" All SS	43,000 GPM	2000

City of Weston, FL	FL, USA	2	42"	40,000 GPM (w/cert. Fact. test)	2000
Sugar Farms Coop (FL Crystals)	FL, USA	2	36"	27,000 GPM	2000
S. Broward Drainage Dist	FL, USA	3	36"	40,000 GPM (w/cert. Fact. test)	2000
S. Florida Water Mgt. Dist	FL, USA	2	36"	27,000 GPM (w/cert. Fact. test)	2000
Ishmael Construction	IL, USA	1	36"	30,000 GPM	2000
Plantation Acres Drainage Dist.	FL, USA	1	30"	20,000 GPM	2000
King Ranch	FL, USA	1	30"	30,000 GPM	2000
CR Pittman Inc.	LA, USA	2	30"	27,000 GPM	2000
Forrest Levee Drainage District	MO, USA	2	30"	27,000 GPM	2000
S. Broward Drainage Dist.	FL, USA	2	30"	31,000 GPM	2000
City of Dania Beach, FL	FL, USA	1	20"	14,000 GPM	2000
Brevard County, FL	FL, USA	1	18" All SS	8,000 GPM	2000
U.S. Dept of Fish and Wildlife	FL, USA	1	14" Mobile	6000 GPM	2000
Brevard County, FL	FL, USA	1	12" All SS	5,000 GPM	2000
Barron Water Control	FL, USA	2	48"	52,500 GPM (w/cert. Field Test)	1999
Aquacorporacion Inter.	Costa Rica	4	42"	45,000 GPM	1999
Gulf Coast Citrus Inc.	FL, USA	1	36"	28,000 GPM	1999
Sugar Farms Coop (FL Crystals)	FL, USA	8	36"	28,000 GPM	1999
Duda & Sons	FL, USA	1	36"	32,000 GPM	1999
Plattville Drainage Dist.	IA, USA	2	36"	32,500 GPM	1999
Boca West Masters Ass.	FL, USA	1	36"	35,000 GPM	1999
Deseret Ranch	FL, USA	1	30"	16,000 GPM	1999
S. Broward Drainage Dist	FL, USA	1	30"	20,000 GPM	1999
Dubois Farms	FL, USA	40	24"-42"	10,000-40,000 GPM	1999
AquaKing Farms	FL, USA	2	24"	12,000 GPM	1999
Sugar Farms Coop (FL Crystals)	FL, USA	2	24"	12,OOOGPM	1999
Industria Nacional	Dom. Rep.	1	24"	17,500 GPM	1999
Cayman Turtle Farm	Cayman Isl	2	14" stage All SS	5,000 GPM	1999
City of Santa Rosa Beach, FL	FL, USA	3	12"	2,500 GPM	1999
IMC Agrico Inc.	FL, USA	5	42"	35,000 GPM	1998

Ishmael Construction	IL, USA	1	36"	30,000 GPM	1998
CFCO	IL, USA	1	30"	25,000 GPM	1998
H&H Sod Farm	FL, USA	1	24"	14,000 GPM	1998
City of Hollywood, FL	FL, USA	3	24"	15,000 GPM	1998
City of Lakeland, FL	FL, USA	1	24"	17,500 GPM	1998
CFCO	IL, USA	1	24"	15,000 GPM	1998
Bedner Growers Inc.	FL, USA	1	24"	15,000 GPM	1998
CFCO	IL, USA	1	20"	11,000 GPM	1998
Town of Jupiter, FL	FL, USA	1	12"	3,800 GPM	1998
City of Hollywood, FL	FL, USA	1	12"	4,500 GPM	1998
Barron Water Control	FL, USA	1	54"	75,000 GPM	1997
Barron Water Control	FL, USA	1	48"	52,500 GPM	1997
City of Hollywood, FL	FL, USA	2	36"	35,000 GPM	1997
Ideker Farms	MO, USA	1	36"	33,000 GPM	1997
Canadian Aquaculture Sys.	Canada	2	36"	29,000 GPM	1997
Duda & Sons	FL, USA	2	36"	32,000 GPM	1997
Deseret Ranch	FL, USA	9	36"	28,000 GPM	1997
Village of Bal Harbour, FL	FL, USA	2	30" All SS	17,500 GPM	1997
Duda & Sons	FL, USA	1	30"	25,000 GPM	1997
Duda & Sons	FL, USA	2	30"	25,000 GPM	1997
City of Tampa, FL	FL, USA	1	30"	11,000 GPM	1997
Duda & Sons	FL, USA	1	24"	16,000 GPM	1997
Indian River Mosquito Dist.	FL, USA	1	16" All SS	6,000 GPM	1997
Duda & Sons	FL, USA	1	16"	6,000 GPM	1997
U.S. Army Corps of Engr.	NE, USA	2	48"	63,500 GPM	1996
Acme Improvement District	FL, USA	4	48"	60,000 GPM	1996
U.S. Army Corps of Engr.	NE, USA	1	48"	44,800 GPM (w/cert. Field Test)	1996
M&L Engine Co.	LA, USA	2	48"	50,000 GPM	1996
S. Broward Drainage Dist	FL, USA	8	42"	50,000 GPM	1996
Talisman Sugar	FL, USA	8	42"	50,000 GPM	1996

Sugar Farms Coop (FL Crystals)	FL, USA	9	36"	25,000 GPM	1996
ALICO Inc.	FL, USA	3	36"	35,000 GPM	1996
Aqua Chame	Panama	10	30"	23,000 GPM	1996
Deseret Ranch	FL, USA	15	30"	20,000 GPM	1996
City of Jacksonville Beach, FL	FL, USA	2	24"	11,500 GPM	1996
Thomas Produce	FL, USA	120	14"-30"	4,000-25,000 GPM	1996
M&L Industries	LA, USA	4	14"	4,000 GPM	1996
EDS Pump	BC, Canada	1	12"	3,000 GPM	1996
Loxahatchee Grove Water Cntrl.	FL, USA	1	42"	50,000 GPM	1995
Boca West Masters Ass.	FL, USA	1	30"	25,000 GPM	1995
R&A Farms	FL, USA	6	30"	20,000 GPM	1995
Jensen of Jacksonville	FL, USA	4	24"	12,000 GPM	1995
Dade County, FL	FL, USA	1	24"	14,500 GPM	1995
Dade County, FL	FL, USA	1	16"	9,000 GPM	1995
Bombas Goulds de Ven.	Venezuela	3	36"	22,014 GPM	1994
Hendry Irrigation	FL, USA	1	36"	25,000 GPM	1994
Evans Properties	FL, USA	10	30"-42"	20,000-40,000 GPM	1994
City of Parkland, FL	FL, USA	1	30"	31,000 GPM	1993
S. Florida Water Mgt. Dist	FL, USA	8	14"	4,500 GPM	1993
St. Charles Parish, LA	LA, USA	1	36"	28,000 GPM	1992
Town of Palm Beach, FL	FL, USA	1	28"	15,000 GPM	1992
St. John River Wtr Mgt	FL, USA	2	24"	18,000 GPM	1992
Town of Palm Beach, FL	FL, USA	1	12"	2,700 GPM	1992
Barron Water Control	FL, USA	6	54"	75,000 GPM	1991
ALICO Inc.	FL, USA	6	54"	75,000 GPM	1990
City of Boca Raton, FL	FL, USA	1	30"	31,000 GPM	1990
City of Fort Lauderdale, FL	FL, USA	2	30"	30,000 GPM	1989
City of Boca Raton, FL	FL, USA	1	30"	25,000 GPM	1989
City of Fort Lauderdale, FL	FL, USA	1	24"	17,500 GPM	1989
Florida Power & Light	FL, USA	1	20"	15,000 GPM	1989

Deerfield Irrigation	FL, USA	3	42"	40,000 GPM	1988
Sunshine Drainage	FL, USA	1	30"	22,000 GPM	1988
Royal Land Development	FL, USA	1	24"	12,000 GPM	1988
Savannah Club	FL, USA	1	24"	12,000 GPM	1987
Farm Credit Leasing	FL, USA	10	20"-30"	10,000-22,000 GPM	1987
Savannah Club	FL, USA	1	16"	8,000 GPM	1987
Sues Pump Rentals	FL, USA	1	30" Hyd.	28,000 GPM	1986
Sues Pump Rentals	FL, USA	2	24" Hyd.	20,000 GPM	1986
Sues Pump Rentals	FL, USA	4	20" Hyd.	15,000 GPM	1986
Sues Pump Rentals	FL, USA	4	18" Hyd.	12,000 GPM	1986
N. Palm Beach Wtr. Control	FL, USA	2	42" Hyd.	35,000 GPM	1985
Fellsmere Farm	FL, USA	1	42"	42,000 GPM	1985
Boca West Masters Ass.	FL, USA	1	42"	42,000 GPM	1985
Fellsmere Farm	FL, USA	1	36"	25,000 GPM	1985
Sawgrass Players Club	FL, USA	3	42"	40,000 GPM	1983
W. Lauderdale Water Control	FL, USA	8	36"	25,000 GPM	1982

Partial Hydraulic Installation List

FPI Inc.
814 Hammondville Road
Pompano Beach, FL 33060
(954) 946-3066 / (954) 946-3111 fax

Customer Name	Location	Units	Size	Year
US Army Corps-Jefferson Parish	LA, USA	3	60" Hyd.	2006
US Army Corps-Jefferson Parish	LA, USA	1	36" Hyd.	2006
US Army Corps-Jefferson Parish	LA, USA	4	24" Hyd.	2006
US Army Corps-Jefferson Parish	LA, USA	5	20" Hyd.	2006
Wellton Mohawk Drainage Dist.	AZ, USA	2	42" Hyd.	2006
Hydradyne Hydraulics	LA, USA	1	30" Hyd.	2004
Republic of China	Taiwan	1	24" HiHead	2003
Terrebonne Parish, LA	LA, USA	2	12" Hyd.	2002
DC Hiatt	FL, USA	2	10" Hyd.	1999
City of Hollywood, FL	FL, USA	1	12" Hyd.	1998
Gilbert Pump	FL, USA	3	8" Hyd.	1998
City of Hollywood, FL	FL, USA	1	12" Hyd.	1998
Gilbert Southern Corp.	FL, USA	2	8" Hyd	1998
Gilbert Southern Corp.	FL, USA	2	6" Hyd.	1998
J. Buglione Construction Inc.	FL, USA	2	6" Hyd.	1998
Daytona Speedway	FL, USA	1	6" Hyd.	1996
M&L Engine	LA, USA	1	12" Hyd.	1996
Public Storage Inc.	FL, USA	1	6" Hyd.	1995
J. Buglione Inc.	FL, USA	1	6" Hyd.	1995
M&L Engine Inc.	LA, USA	4	14" Hyd.	1994
M&L Engine Inc.	LA, USA	1	12" Hyd.	1994
Hardy Brothers Inc.	FL, USA	2	6" Hyd.	1994
Solid Waste Authority	FL, USA	1	4" Hyd.	1994
Terrebonne Parish, LA	LA, USA	3	16" Hyd.	1993

Terrebonne Parish, LA	LA, USA	1	12" Hyd.	1993
Dayco Astaldi	FL, USA	3	4" Hyd.	1992
St. Johns River Water Control Distric	FL, USA	2	24" HiHead Hyd.	1992
ACME Drainage District	FL, USA	1	12" Hyd.	1991
Strazulla Holdings	FL, USA	1	20" Hyd.	1990
DC Hiatt Construction	FL, USA	1	8" Hyd	1990
N. Carolina Dept. of Corr.	NC, USA	1	20" Hyd.	1989
City of Boca Raton, FL	FL, USA	1	30" Hyd.	1989
Waste Management Inc.	FL, USA	1	6" Hyd.	1989
Fore Golf Development	FL, USA	1	16" Hyd.	1988
Broward County, FL	FL, USA	2	6" Hyd.	1988
Royal Land Development	FL, USA	1	24" Hyd.	1988
Sunshine Drainage District	FL, USA	1	30" Hyd.	1988
Savannah Club Developments	FL, USA	1	24" Hyd.	1987
Savannah Club Developments	FL, USA	1	16" Hyd.	1987
Sues Pump Rentals Inc.	FL, USA	1	30" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	2	24" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	4	20" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	4	18" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	2	16" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	4	14" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	4	12" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	7	8" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	20	6" Hyd.	1986
Sues Pump Rentals Inc.	FL, USA	1	6" Hyd.	1985
Sues Pump Rentals Inc.	FL, USA	8	4" Hyd.	1985
N. Palm Beach Improvement Dist.	FL, USA	2	42" Hyd.	1985
Zeni Drilling	FL, USA	1	16" Hyd.	1984
Wright & Lopez Inc.	FL, USA	1	6" Hyd.	1984

November 18, 2010

Partial Hydraulic Installation Reference List

Location:	Georgetown, SC
Year:	2010/2011
Project Name:	City of Georgetown
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	2
Pump Size:	48x42
Pump Capacity:	67500gpm
Total Dynamic Head:	16.2ft
Engine HP:	575hp
Contact:	Mr. Steve Hirsch 843-554-8602

Completed on time & within budget without incident

Location:	Plaquamine Parish, LA
Year:	2008
Project Name:	Plaquamine Parish
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	3
Pump Size:	30x30
Pump Capacity:	21667 gpm
Total Dynamic Head:	18ft
Engine HP:	166hp
Contact:	Mr. Ed Parson – 504-733-1330

Completed on time & within budget without incident

Location:	St. Charles Parish, LA
Year:	2008
Project Name:	St. Charles Parish
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	2
Pump Size:	30x30
Pump Capacity:	21667 gpm
Total Dynamic Head:	18ft
Engine HP:	166hp
Contact:	Mr. Ed Parson – 504-733-1330

Completed on time & within budget without incident

FPI Inc.
911 East Atlantic Blvd. #107
Pompano Beach, FL 33060
(954) 946-3066 /(954) 946-3111 fax
sales@fpipumps.com / www.fpipumps.com

Location:	Jefferson Parish, LA
Year:	2006
Project Name:	Hoey's Basin Project
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	3
Pump Size:	60x54
Pump Capacity:	107,712 gpm
Total Dynamic Head:	14ft
Engine HP:	700hp
Contact:	Mr. Ali Pirsalehy – Engineering 504-736-6731

Completed on time & within budget without incident

Location:	Jefferson Parish, LA
Year:	2006
Project Name:	Hoey's Basin Project
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	1
Pump Size:	42x36
Pump Capacity:	35,904 gpm
Total Dynamic Head:	23ft
Engine HP:	425hp
Contact:	Mr. Ali Pirsalehy – Engineering 504-736-6731

Completed on time & within budget without incident

Location:	Wellton, AZ
Year:	2006
Project Name:	Wellton Mohawk Irrigation and Drainage District
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	2
Pump Size:	42x36
Pump Capacity:	44,880 gpm
Total Dynamic Head:	16.2ft
Engine HP:	320hp
Contact:	Mr. Gary Langford 928-785-3351

Completed on time & within budget without incident

Location:	Palm Beach, FL
Year:	1986
Project Name:	Northern Palm Beach County Water Control District
Type:	Diesel engine/electric motor hydraulically driven propeller pumps
Qty.	2
Pump Size:	42x36
Pump Capacity:	50,000 gpm
Total Dynamic Head:	7.0ft
Engine HP:	135hp
Contact:	Mr. Rick Musgrove 561-624-7830

Completed on time & within budget without incident

Location:	Boca Raton, FL
Year:	1989
Project Name:	City of Boca Raton
Type:	Diesel engine hydraulically driven propeller pumps
Qty.	1
Pump Size:	30x30
Pump Capacity:	25000 gpm
Total Dynamic Head:	7.4ft
Engine HP:	100hp
Contact:	Mr. Ramy Maharaj 561-338-7373

Completed on time & within budget without incident